

Unclassified

1a REPORT S	REPORT DOCUMENTATION			Exp D			Date Jun	
171	ECURITY CLASSIFI	CATION		16 RESTRICTIVE	MARKINGS			
Unclassi	CLASSIFICATION A	ALITHORITY		2 DISTRIBUTION	N/AVAILABILITY	OF BEBO	O.T	
.u Jecomitt	CASSIFICATION /	- OTRORIT						410+-1
26 DECLASSIF	DECLASSIFICATION / DOWNGRADING SCHEDULE		Approved for public release; distribunited.					
PERFORMIN	IG ORGANIZATIOI	N REPORT NUMB	ER(S)	5 MONITORING ORGANIZATION REPORT NUMBER(S)				
Technica	1 Report RE	MR-CO-6						
USAEWES,	OF PERFORMING ORGANIZATION CS, Coastal Engineering (If applicable) Cch Center		7a NAME OF MONITORING ORGANIZATION					
6c. ADDRESS	(City, State, and a	ZIP Code)		7b. ADDRESS (C	ity, State, and Zi	P Code)		
PO Box 6	31							
Vicksbur	g, MS 39180	0-0631		1				
	FUNDING / SPONS	ORING	Bb OFFICE SYMBOL	9 PROCUREMEN	NT INSTRUMENT	IDENTIFIC	ATION N	UMBER
ORGANIZA	alion Corps of Eng	ginec==	(If applicable)					
	City, State, and Zi		1	10 source or	FUNDING NUMB	FRS		
UC. AUDRESS (city, state, and Zi	ir code)		PROGRAM	PROJECT	TASK		WOR
Washingt	on, DC 203	14-1000		ELEMENT NO	NO	NO		ACCES
3-		, .		1		-		3
Stabilit Breakwat	ude Security Class y of Dolos (er and Jett	Overlays fo	r Rehabilitatio bjected to Brea	n of Tribar- king Waves	Armored Rub	ble-Mo	ound	
		wright, Bre	nda J.					
	, .							
Carver,	REPORT	13b TIME (OVERED	14 DATE OF REP		h, Day)	15 PAGE	COUNT
Carver,	REPORT	13b TIME (COVERED TO	14 DATE OF REP August 19		h, Day)	15 PAGE 35	COUNT
Carver, 13a TYPE OF Final re- 16 SUPPLEME	REPORT POTE NTARY NOTATIO	FROM_ N A report	of the Coastal	August 198	88 a of the Re	pair,	35 Evalua	tion,
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance,	REPORT port NTARY NOTATIO and Rehabil	FROM_ N A report itation (RI	of the Coastal	August 198 problem area rogram. Avai	88 a of the Re ilable from	pair,	35 Evalua	tion,
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat	REPORT port ENTARY NOTATIO and Rehabil ion Service.	FROM N A report itation (RI 5285 Port	of the Coastal EMR) Research P Royal Road, Sp	August 198 problem area rogram. Avai	88 of the Replication A 22161.	pair, Natio	35 Evalua nal Te	tion,
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat	REPORT port NTARY NOTATIO and Rehabil ton Service. COSATI CO	FROM_ N A report itation (RI 5285 Port	of the Coastal EMR) Research P Royal Road, Sp	August 190 problem area rogram. Avairingfield, VA	88 a of the Reilable from A 22161. rse if necessary a	pair, Natio	35 Evalua nal Te	tion, chnica
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat	REPORT port ENTARY NOTATIO and Rehabil ion Service.	FROM N A report itation (RI 5285 Port	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit	August 190 problem area rogram. Avai ringfield, VA (Continue on revers	88 a of the Reilable from A 22161. rse if necessary a Jetties	pair, Natio	35 Evalua nal Te	tion, chnica
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat	REPORT port NTARY NOTATIO and Rehabil ton Service. COSATI CO	FROM_ N A report itation (RI 5285 Port	of the Coastal EMR) Research P Royal Road, Sp	August 190 problem area rogram. Avai ringfield, VA (Continue on revers	88 a of the Reilable from A 22161. rse if necessary a	pair, Natio	35 Evalua nal Te	tion, chnica
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat: 17 FIELD	REPORT port ENTARY NOTATIO and Rehabil on Service. COSATI CO GROUP	FROM	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater	August 190 problem area rogram. Avai ringfield, VA (Continue on revei s s '	88 a of the Reilable from A 22161. rse if necessary a Jetties	pair, Natio	35 Evalua nal Te	tion, chnic
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat: 17 FIELD	REPORT port ENTARY NOTATIO and Rehabil on Service. COSATI CO GROUP	FROM	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit	August 190 problem area rogram. Avai ringfield, VA (Continue on revei s s '	88 a of the Reilable from A 22161. rse if necessary a Jetties	pair, Natio	35 Evalua nal Te	tion, chnice
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informati 17 FIELD 19 ABSTRACT An overlays	REPORT port NTARY NOTATIO and Rehabil on Service. COSATI CO GROUP (Continue on re- experimenta used to ref	FROM	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater	August 190 problem area rogram. Avai ringfield, VA (Continue on rever s s number) conducted to rubble-mound	a of the Reilable from A 22161. rse if necessary a Jetties Rubble mo	pair, Natio	35 Evalua nal Te	ck number
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informati 17 FIELD 19 ABNIRACI An overlays	REPORT port ENTARY NOTATIO and Rehabil ton Service. COSATI CO GROUP (Continue on re experimenta used to rel to breaking The stabil	FROM	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater y and identify by brock vestigation was tribar-armored was concluded cient is indepe	August 190 problem area rogram. Avai ringfield, VA (Continue on rever s s number) conducted to rubble-mound that:	a of the Reilable from A 22161. rse if necessary a Jetties Rubble mo	pair, Natio nd identification und sign g and j	35 Evalua nal Te	ce for
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informat; 17 FIELD 19 ABNRACT An overlays subject	REPORT port NTARY NOTATIO and Rehabilion Service. COSATI CO GROUP (Continue on ret experimenta used to ret to breaking The stabilly on 1.5% Stability occurring	PROM (RI 5285 Port octs) SUB-GROUP Verse if necessary all model in thabilitate waves. It lity coeffil and IV on showed some at the low	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater y and identify by brock vestigation was tribar-armored was concluded cient is indepe	August 190 problem area rogram. Avai ringfield, VA (Continue on revers s ' number) conducted to rubble-mound that: ndent of sea-	a of the Reilable from A 22161. rse if necessary a Jetties Rubble mo o obtain de breakwater -side struc	pair, Natio nd identification und sign g and j ture s ith mi	35 Evalua nal Te fy by blo guidance etty t slope f	ce for slostabi
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informati 17 FIELD 19 ABSTRACT An overlays subject a.	REPORT PORT PORT NTARY NOTATIO and Rehabil ON Service. COSATI CO GROUP (Continue on rel experimenta used to rel to breaking The stabil IV on 1.58 Stability occurring wave perio	PROM N A report itation (RI 5285 Port DES SUB-GROUP verse if necessary al model in habilitate waves. It lity coeffi H and IV on showed som at the low ods in shall im stabilit;	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater y and identify by block vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of de	August 190 problem area rogram. Avai ringfield, VA (Continue on revers s number) conducted to rubble-mound that: ndent of sea- both d/L a /L and highe	a of the Reilable from A 22161. rse if necessary a Jetties Rubble mo o obtain de breakwater -side structure and H/d wer values o	pair, Natio nd identi und sign g and j ture s ith mif	35 Evalua nal Te fy by blo guidance guidance tetty to slope f	ce for rrunks for sl
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informati 17 FIELD An overlays subject a. b.	REPORT port NTARY NOTATIO and Rehabil ion Service. COSATI CO GROUP (Continue on released to relate to breaking The stabil IV on 1.58 Stability occurring wave perio	PROM N A report itation (RI 5285 Port DES SUB-GROUP verse if necessary al model in habilitate waves. It lity coeffi H and IV on showed som at the low ods in shal im stabilit ruction.	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater and identify by brock vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of d lower water. y coefficient o	August 196 problem area rogram. Avai ringfield, VA (Continue on rever s s ' number) conducted to rubble-mound that: ndent of sea- both d/L a /L and highe	a of the Reilable from A 22161. rse if necessary a Jetties Rubble mo o obtain de breakwater -side structure and H/d wer values o	pair, Natio nd identi und sign g and j ture s ith mi f H/d	35 Evalua nal Te fy by blo guidance guidance tetty to slope f	ce for rrunks for sl
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Informati 17 FIELD 19 ABSTRACT An overlays subject a. b.	REPORT PORT PORT PORT NTARY NOTATIO and Rehabil ON Service. COSATI CO GROUP (Continue on released to relate to breaking The stabil IV on 1.58 Stability occurring wave period The minimum new constr	PROM N A report Litation (RI 5285 Port DES SUB-GROUP Verse if necessary al model in habilitate waves. It lity coeffi H and IV on showed som at the low ods in shal lum stabilit ruction.	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater and identify by block vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of d lower water. y coefficient o	August 196 problem area rogram. Avai ringfield, VA (Continue on rever s ' number) conducted to rubble-mound that: ndent of sea- both d/L a /L and higher bserved signs	a of the Reilable from A 22161. The if necessary a Jetties Rubble mo o obtain de breakwater — side structure and H/d wer values o ificantly e	pair, Natio nd identi und sign g and j ture s ith mi f H/d	35 Evalua nal Te fy by blo guidance guidance tetty to slope f	ce for rrunks stabi
Carver, 13a TYPE OF Final revenue of Supplementation of Supplementati	REPORT PORT PORT PORT PORT PORT PORT PORT	FROM N A report Litation (RI 5285 Port DES SUB-GROUP Verse if necessary al model in habilitate waves. It lity coeffi H and IV on showed som at the low ods in shal lim stabilit ruction.	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater and identify by brock vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of d lower water. y coefficient o	August 196 problem area rogram. Avai ringfield, VA (Continue on rever s s ' number) conducted to rubble-mound that: ndent of sea- both d/L a /L and highe bserved sign:	a of the Reilable from A 22161. The if necessary a Jetties Rubble mo o obtain de breakwater — side structure and H/d wer values o ificantly e	pair, Natio nd identi und sign g and j ture s ith mif f H/d xceeds	35 Evalua nal Te fy by blo guidance ietty t slope f nimum i, i.e	ce for sl stabi
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Information 17 FIELD 19 ABSTRACT An overlays subject a. b. C. 20 DISTRIBUTION CLASS 22a NAME OF FINAL CLASS 22	REPORT PORT PORT PORT PORT PORT PORT PORT	FROM N A report Litation (RI 5285 Port DES SUB-GROUP Verse if necessary al model in habilitate waves. It lity coeffi H and IV on showed som at the low ods in shal lim stabilit ruction.	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater and identify by brock vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of d lower water. y coefficient o	August 196 problem area rogram. Avai ringfield, VA (Continue on rever s s ' number) conducted to rubble-mound that: ndent of sea- both d/L a /L and highe bserved sign:	a of the Reilable from A 22161. The second free structure of the structur	pair, Natio nd identi und sign g and j ture s ith mif f H/d xceeds	35 Evalua nal Te fy by blo guidance ietty t slope f nimum i, i.e	ce for sl stabi
Carver, 13a TYPE OF Final re 16 SUPPLEME tenance, Information 17 FIELD 19 ABSTRACT An overlays subject a. b. C.	REPORT PORT PORT PORT PORT PORT PORT PORT	FROM N A report Litation (RI 5285 Port DES SUB-GROUP Verse if necessary al model in habilitate waves. It lity coeffic H and IV on showed som at the low ods in shal lim stabilit ruction. TY OF ABSTRACT SAME AS NOIVIDUAL	of the Coastal EMR) Research P Royal Road, Sp 18 SUBJECT TERMS Armor unit Breakwater and identify by brock vestigation was tribar-armored was concluded cient is indepe 2H. e dependency on er values of d lower water. y coefficient o	August 196 problem area rogram. Avai ringfield, VA (Continue on rever s s number) conducted to rubble-mound that: ndent of sea- both d/L a /L and highe bserved signi	a of the Reilable from A 22161. The if necessary a Jetties Rubble mo to obtain de breakwater side struction and H/d were values of the struction of the struct	pair, Natio nd identi und sign g and j ture s ith mi f H/d xceeds	35 Evalua nal Te fy by blo guidance ietty t slope f nimum i, i.e	ce for sl stabi

PREFACE


Authority to carry out this investigation was granted the US Army Engineer Waterways Experiment Station's (WES's) Coastal Engineering Research Center (CERC) by the Office, Chief of Engineers (OCE) under the Repair, Evaluation, Maintenance, and Rehabilitation (REMR) Research Program Work Unit 32325, "Use of Dissimilar Armor for Repair and Rehabilitation of Rubble-Mound Coastal Structures."

Tests of dolos overlays for existing tribar armor, which fulfill one milestone of this work unit, were conducted under the general direction of Mr. James E. Crews and Tony C. Liu, REMR Overview Committee, OCE; Mr. Jesse A. Teiffer, Jr., Directorate of Research and Development, OCE; members of the REMR Field Review Group; Mr. John H. Lockhart, Jr., Coastal Technical Monitor, OCE; Mr. William F. McCleese, REMR Program Manager, WES; and Mr. D. D. Davidson, REMR Coastal Program Area Leader, CERC.

The study was conducted by personnel of CERC under the general direction of Dr. James R. Houston, Chief, CERC, and Mr. Charles C. Calhoun, Jr., Assistant Chief, CERC; and under direct supervision of Mr. C. E. Chatham, Chief, Wave Dynamics Division, and Mr. D. D. Davidson, Chief, Wave Research Branch. Tests were planned by Mr. Robert D. Carver, Principal Investigator, and Ms. Brenda J. Wright, Civil Engineering Technician. The model was operated by Ms. Wright, under the supervision of Mr. Carver. This report was prepared by Mr. Carver and Ms. Wright and edited by Ms. Shirley A. J. Hanshaw, Information Products Division, Information Technology Laboratory, WES.

Director of WES during report publication was COL Dwayne G. Lee, CE. Technical Director was Dr. Robert W. Whalin.





CONTENTS

	Page
PREFACE	1
CONVERSION FACTORS, NON-SI TO SI (METRIC) UNITS OF MEASUREMENT	3
PART I: INTRODUCTION	4
Background	5
PART II: TESTS	6
Stability Scale Effects Test Procedures Test Equipment Selection of Test Conditions	6
PART III: TEST RESULTS	
PART IV: CONCLUSIONS	
REFERENCES	18
TABLE 1	
PHOTOS 1-11	
APPENDIX A: NOTATION	A1

CONVERSION FACTORS, NON-SI TO SI (METRIC) UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI (metric) units as follows:

Multiply	Ву	To Obtain		
feet	0.3048	metres		
inches	25.4	millimetres		
pounds (mass)	0.4535924	kilograms		
pounds (mass) per cubic foot	16.01846	kilograms per cubic metre		
square feet	0.09290304	square metres		



STABILITY OF DOLOS OVERLAYS FOR REHABILITATION OF TRIBAR-ARMORED RUBBLE-MOUND BREAKWATER AND JETTY TRUNKS SUBJECTED TO BREAKING WAVES

PART I: INTRODUCTION

Background

- l. The experimental investigation described herein constitutes a portion of a research effort to provide engineering data for the effective and economical rehabilitation of rubble-mound breakwaters and jetties. In this study, a rubble-mound breakwater or jetty is defined as a protective structure constructed with a core of quarry-run stone, sand, or slag and protected from wave action by one or more stone underlayers and a cover layer composed of selected quarrystone or specially shaped concrete armor units.
- 2. Previous investigations, under Work Unit 31269, "Stability of Breakwaters," have yielded a significant quantity of design information for new construction using quarrystone (Hudson 1958 and Carver 1980 and 1983), tetrapods, quadripods, tribars, modified cubes, hexapods, and modified tetrahedrons (Jackson 1968), dolosse (Carver and Davidson 1977 and Carver 1983), and toskane (Carver 1978). Rehabilitation projects on several of the Corps' rubble-mound structures have revealed a total lack of design guidance or even information concerning the interfacing and stability response of armor units that are of dissimilar type and/or size. In the past, selection of new armor type, method of interfacing, and procedures for preparation of the existing section have been based on engineering judgment or, in more recent times, on site-specific model studies. The engineering judgment process can be expensive since experience is limited and there is not usually a solid basis for it. This process can lead to recurring failures that cost millions of dollars without a real solution being developed for the long-term problem. Sitespecific model studies have provided good singular solutions, but sitespecific data usually fail to meet the requirements of other projects (Carver, in preparation). It is anticipated that the problem will become more acute in future years as rehabilitation of major breakwaters and jetties becomes necessary to extend their project life or to meet greater design demands.

Approach

3. Model breakwaters and armor units are being used to experimentally investigate the stability response of various armor combinations for selected structure geometries and wave conditions. It would be an extremely extensive task to comprehensively investigate all different types of existing armor units; therefore, this research effort will address only the three types (stone, dolos, and tribars) of armor most commonly used in the Corps. Selection of these armor types should give test results the widest range of applicability possible. Tests will be conducted with breaking wave conditions on no-damage, no-overtopping breakwater trunk and head sections using sea-side slopes of IV:1.5H and IV:2H. Test results for dolos and tribar overlays of existing stone armor and dolos overlays of existing dolos have been reported (Carver and Wright 1987a and 198/b).

Purpose of Study

- 4. The purpose of the present investigation was to obtain design guidance for dolos overlays used to rehabilitate tribar-armored rubble-mound breakwater and jetty trunks subjected to breaking waves. More specifically, it was desired to determine the minimum weight of individual armor units (with given specific weights) required for stability as a function of:
 - a. Sea-side slope of the structure.
 - b. Wave period.
 - c. Wave height.
 - d. Water depth.

PART II: TESTS

Stability Scale Effects

5. If the absolute sizes of experimental breakwater materials and wave dimensions become too small, flow around the armor units enters the laminar regime; and the induced drag forces become a direct function of the Reynolds number. Under these circumstances prototype phenomena are not properly simulated, and stability scale effects are induced. Hudson (1975) presents a detailed discussion of the design requirements necessary to ensure the preclusion of stability scale effects in small-scale breakwater tests and concludes that scale effects will be negligible if the Reynolds stability number $(R_N)^*$

$$R_{N} = \frac{g^{1/2}H^{1/2}l_{a}}{v}$$

where

 $g = acceleration due to gravity, ft/sec^2$

H = wave height, ft

 ℓ_a = characteristic length of armor unit, ft

v = kinematic viscosity

is equal to or greater than 3×10^4 . For all tests reported herein, the sizes of experimental armor and wave dimensions were selected such that scale effects were insignificant (i.e., R_N was greater than 3×10^4).

Test Procedures

Method of constructing test sections

6. All experimental breakwater sections were constructed to reproduce as closely as possible results of the usual methods of constructing full-scale breakwaters. The core material was dampened as it was dumped by bucket or shovel into the flume and was compacted with hand trowels to simulate natural consolidation resulting from wave action during construction of the prototype

^{*} For convenience, symbols and unusual abbreviations are listed and defined in the Notation (Appendix A).

structure. Once the core material was in place, it was sprayed with a low-velocity water hose to ensure adequate compaction of the material. The underlayer stone then was added by shovel and smoothed to grade by hand or with trowels. No excessive pressure or compaction was applied during placement of the underlayer stone. Armor units used in the cover layers were placed in a random manner corresponding to work performed by a general coastal contractor, i.e., they were individually placed but were laid down without special orientation or fitting. After each test series the armor units were removed from the breakwater, all of the underlayer stones were replaced to the grade of the original test section, and the armor was replaced.

Selection of critically breaking waves

- 7. For a given wave period and water depth, the most detrimental breaking wave (i.e. the most damaging wave) was determined by increasing the stroke adjustment on the wave generator in small increments and observing which wave produced the most severe breaking wave condition on the experimental structures. Wave heights of lower amplitude did not form the critical breaking wave, and wave heights of larger amplitude would break seaward of the test structures and dissipate their energy so that they were less damaging than the critically tuned wave.
- 8. A typical stability test series consisted of subjecting the test sections to attack by waves of given heights and periods until all damage had abated or the structures failed. Test sections were subjected to wave attack in approximately 30-sec intervals between which the wave generator was stopped and the waves allowed to decay to zero height. This procedure was necessary to prevent the structures from being subjected to an undefined wave system created by reflections from the experimental breakwater and wave generator. Newly built test sections were subjected to a short duration (five or six 30-sec intervals) of shakedown using a wave equal in height to about one-half of the design wave. This procedure provided a means of allowing consolidation and armor unit seating simulating that which would normally occur during prototype construction.

Method of determining damage

9. To evaluate and compare breakwater stability test results, it is necessary to quantify the changes that have taken place in a given structure during attack by waves of specified characteristics. The US Army Engineer Waterways Experiment Station (WES) developed a method of measuring the

percentage of dama; incurred by a test section during the early 1950's. This method has proven satisfactory and was used as a means for analyzing and comparing the stability tests delineated herein.

sectional area occupied by armor units be determined for each stability test section. Armor unit area is computed from elevations (soundings) taken at closely spaced grid-point locations before the armor is placed on the underlayer, after the armor has been placed but before the section has been subjected to wave attack, and finally after wave attack. Elevations are obtained with a sounding rod equipped with a circular spirit level for plumbing, a scale graduated in thousandths of a foot, and a ball-and-socket foot for adjustment to the irregular surface of the breakwater slope. The diameter in inches of the circular foot of the sounding rod was related to the size of the material being sounded by the following equation:

Diam =
$$C\left(\frac{W_a}{Y_a}\right)^{1/3}$$

where

C = coefficient

 $W_a =$ weight of an armor unit, 1b

 γ_a = specific weight of armor unit, pcf

C = 6.8 for tribars and stone and 13.7 for dolosse. A series of sounding tests in which both the weight of the armor and the diameter of the sounding foot were varied indicated that the above relation would give a measured thickness which visually appeared to represent an acceptable two-layer thickness.

11. Sounding data for each test section were obtained as follows: after the underlayer was in place, soundings were taken on the slopes of the structure along rows beginning at and parallel to the longitudinal center line of the structure and extending in 0.25-ft* horizontal increments until the edge of the armor was reached. On each parallel row, sounding points, spaced

^{*} A table of factors for converting non-SI units of measurement to SI metric units is presented on page 3.

at 0.25-ft increments, were measured. The 0.5 ft of structure next to each wall was not considered because of the possibility of discontinuity effects between armor units and the flume walls. Soundings were taken at the same points once the armor was in place and again after the structure had been subjected to wave attack.

12. Sounding data from each stability test were reduced in the following manner. The individual sounding points obtained on each parallel row were averaged to yield an average elevation at the bottom of the armor layer before the armor was placed and then at the top of the armor layer before and after testing. From these values, the cross-sectional armor area before testing and the area from which armor units were displaced (either downslope or off the section) were calculated. Damage then was determined from the following relation:

Percent damage =
$$\frac{A_2}{A_1}$$
 (100)

where

 A_1 = area before testing, ft²

 A_2 = area from which armor units have been displaced, ft² The percentage given by the WES sounding technique is, therefore, a measurement of an end area which converts to an average volume of armor material that has been moved from its original location (either downslope or off structure).

Test Equipment

13. All tests were conducted in a 5-ft-wide, 4-ft-deep, 119-ft-long concrete wave flume with test sections installed about 90 ft from a vertical displacement wave generator. A thin divider was installed in the center of the test section area, thus yielding two 2.5-ft-wide sections. The first 10-ft length of flume bottom, immediately seaward of the test sections, was molded on a IV-on-10H slope, while the remaining 80-ft length was flat. The generator is capable of producing sinusodial waves of various periods and heights. For all tests, waves of the required characteristics were generated by varying the frequency and amplitude of the plunger motion. Changes in water surface elevation as a function of time (wave heights) were measured by

electrical wave height gages in the vicinity of where the toe of the test sections was to be placed (without the structure in place) and recorded on chart paper by an electrically operated oscillograph. The electrical output of the wave gages was directly proportional to their submergence depth.

Selection of Test Conditions

- 14. Breaking wave tests were conducted using dolos overlays. A review of past site-specific stability projects and hydrographic data showed that typical prototype sea-bottom slopes could range from almost flat to as steep as IV on 10H. Realizing that wave deformation and severity of breaking action increases as bottom slope increases, and since time constraints would allow testing of only one slope, it was decided to use a IV-on-10H slope, thus ensuring severe depth-limited breaking wave action (plunging breakers). When breaking directly on the structure, this type of wave normally causes the most damage to rubble-mound structures.
- 15. By nondimensionalizing design conditions from site-specific projects; it was found that a relative depth (d/L) range of 0.4 to 0.14 should include most prototype conditions encountered in breaking wave stability designs. A review of capabilities of the available flume and wave generator showed that this range of d/L values could be achieved for a reasonable range of testing depths.
- 16. The wave flume was calibrated for depths from 0.40 to 1.00 ft in 0.05-ft increments at d/L values of 0.04, 0.06, 0.08, 0.10, 0.12, and 0.14. This range of depths, and consequently breaking wave heights, proved to be compatible with the selected armor weights and sea-side breakwater slopes.
- 17. All stability tests were conducted on sections of the type shown in Figure 1 and Photos 1-4. Sea-side slopes of 1V on 1.5H and 1V on 2H were investigated, while the beach-side slope was held constant at 1V on 1.5H. Heights of the simulated existing structures (prior to placement of the dolos overlays) varied from 1.0 to 1.2 ft. The height necessary to prevent wave overtopping of the existing structure was determined from the slopes, water depths, and wave heights investigated in determining stability coefficients for the dissimilar armor overlays.
- 18. It was assumed that the overlaying dolos armor could be slightly to significantly smaller than the existing tribars. A review of existing model

1,5 VARIES 1.5, 2

BEACH SIDE

SEA SIDE



EXISTING TRIBAR ARMOR-

- UNDERLAYER -

CORE

Figure 1. Typical breakwater cross section

materials was made in concert with this assumption, and 0.627-1b tribars were selected to simulate existing conditions. Tribars were randomly placed in two layers. Overlaying dolos weights of 0.442 and 0.589 1b were used.

PART III: TEST RESULTS

19. Various combinations of wave height and period and water depth were investigated for the selected armor weights and structure slopes. Some of these conditions proved to be too severe, i.e., they produced excessive damage as measured by the sounding method. Conversely, some conditions proved to be conservative. Results of those tests which yielded stable design conditions are summarized in Table 1. Presented therein are experimentally determined design wave heights and calculated stability coefficients K_D 's as functions of relative depth d/L and relative wave heights H/d. The stability coefficient K_D is determined from the Hudson formula, i.e.,

$$W_{a} = \frac{\gamma_{a}H^{3}}{K_{D}(S_{a} - 1)^{3} \cot \alpha}$$

where


 K_{n} = stability coefficient

S_a = specific gravity of armor unit

 α = reciprocal of breakwater slope

Armor units were placed randomly in two layers, and the number of armor units per given surface area was equal to that presently recommended for new construction in EM 1110-2-2904 (Headquarters, Department of the Army 1986). Photos 5-11 show typical after-testing conditions of the structures.

- 20. Figures 2 and 3 present $K_{\overline{D}}$ as a function of d/L , H/d , and sea-side structure slope. These data show the stability coefficient to be independent of sea-side structure slope; however, a slight dependency on both d/L and H/d is observed with minimum stability occurring at the lower values of d/L and higher values of H/d , i.e. longer wave periods in shallower water.
- 21. The minimum stability coefficient (20) observed in the present investigation is very significant. Previous tests of dolos overlays for existing stone armor (Carver and Wright 1988a) and existing dolosse (Carver and Wright 1988b) yielded minimum stability coefficients of 12 and 15. Thus, the obtained value of 20 significantly exceeds that observed for other dissimilar armor combinations and present recommendations for new construction ($K_{\rm D} = 15$).







Figure 2. Stability coefficient ($K_{\overline{D}}$) versus relative depth (d/L)






Figure 3. Stability coefficient $(K_{\overline{D}})$ versus relative wave height (H/d)

Therefore, due to superior stability, a tribar dolos combination might be considered for new construction.

PART IV: CONCLUSIONS

- 22. Based on tests and results described herein in which dolos armor is used to overlay existing tribars on breakwater trunks subjected to breaking waves with a direction of approach of 90 deg, it is concluded that:
 - a. The stability coefficient is independent of sea-side structure slope for slopes of 1V on 1.5H and 1V on 2H.
 - \underline{b} . Stability showed some dependency on both d/L and H/d with minimum stability occurring at the lower values of d/L and higher values of H/d , i.e. longer wave periods in shallower water.
 - <u>c</u>. The minimum stability coefficient observed significantly exceeds that obtained for new construction.

REFERENCES

- Carver, R. D. 1978 (Jun). "Hydraulic Model Tests of Toskane Armor Units," ETL 1110-2-233, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- . 1980 (Jan). "Effects of First Underlayer Weight on the Stability of Stone-Armored Rubble-Mound Breakwater Trunks Subjected to Nonbreaking Waves with No Overtopping; Hydraulic Model Investigation," Technical Report HL-80-1, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- . 1983 (Dec). "Stability of Stone- and Dolos-Armored, Rubble-Mound Breakwater Trunks Subjected to Breaking Waves with No Overtopping," Technical Report CERC-83-5, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- . In preparation. "Prototype Experience with the Use of Dissimilar Armor for Repair and Rehabilitation of Rubble-Mound Coastal Structures." Technical Report REMR-CO-2, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Carver, R. D., and Davidson, D. D. 1977 (Nov). "Dolos Armor Units Used on Rubble-Mound Breakwater Trunks Subjected to Nonbreaking Waves with No Overtopping," Technical H-77-19, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Curver, R. D., and Wright, B. J. 1988a (Feb). "Stability of Dolos and Tribar Overlays for Rehabilitation of Stone-Armored, Rubber-Mound Breakwater and Jetty Trunks Subjected to Breaking Waves," Technical Report REMR-CO-4, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Carver, R. D., and Wright, B. J. 1988b (Jun). "Stability of Dolos Overlays for Rehabilitation of Dolos-Armored, Rubble-Mound Breakwater and Jetty Trunks Subjected to Breaking Waves," Technical Report REMR-CO-5, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Hudson, R. Y. 1958 (Jul). "Design of Quarry-Stone Cover Layers for Rubble-Mound Breakwaters; Hydraulic Laboratory Investigation," Research Report No. 2-2, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- . 1975 (Jun). "Reliability of Rubble-Mound Breakwater Stability Models; Hydraulic Model Investigation," Miscellaneous Paper H-75-5, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Jackson, R. A. 1968 (Jun). "Design of Cover Layers for Rubble-Mound Break-waters Subjected to Nonbreaking Waves; Hydraulic Laboratory Investigation," Research Report No. 2-11, US Army Engineer Waterways Experiment Station, Vicksburg, MS.
- Headquarters, US Army Corps of Engineers. 1986 (Aug). "Engineering and Design; Design of Breakwaters and Jetties," EM 1110-2-1904, Washington, DC.

Table 1 Values of H , d/L , H/d , and $K_{\overline{D}}$ for Dolos Overlays of Existing Tribar Armor Subjected to Breaking Waves

W _a , 1b	d, ft	T, sec	H, ft	d/L	н/д	KD
		1V-on-1.5H	Structure S	lope		
0.442	0.60	2.32	0.58	0.06	0.97	21.0
0.442	0.95	1.37	0.61	0.14	0.64	24.5
0.589	0.70	1.57	0.63	0.10	0.90	19.9
0.589	0.70	1.92	0.63	0.08	0.90	19.9
0.589	0.90	1.52	0.64	0.12	0.71	20.8
		1V-on-2H	Structure Slo	ope		
0.442	0.65	2.42	0.63	0.06	0.97	20.2
0.442	0.70	1.57	0.63	0.10	0.90	20.2
0.442	0.70	1.92	0.63	0.08	0.90	20.2
0.442	0.90	1.52	0.64	0.12	0.71	21.2
0.589	0.75	1.99	0.70	0.08	0.93	20.5
0.589	0.85	1.73	0.71	0.10	0.84	21.4
0.589	0.95	1.56	0.72	0.12	0.76	22.3
0.589	1.00	1.40	0.72	0.14	0.72	22.3






Photo 1. End view of a typical test section before wave attack at a IV-on-1.5H sea-side structure slope; $_{\rm W}$ = 0.442 lb




CONTRACTOR DECEMBER | DECEMBER |


Sea-side view of a typical test section before wave attack at 1V-on-1.5H sea-side structure slope; $W_a=0.442$ lb Photo 2.



End view of a typical test section before wave attack at a IV-on-2H sea-side structure slope; $V_a=0.589\ Ib$ Photo 3.




Sea-side view of a typical test section before wave attack at a 1V-on-2H sea-side structure slope; $W_a=0.589$ lb Photo 4.



recession because the property

d = 0.95 ft; End view after attack of 1.37-sec, 0.61-ft waves; W_A = 0.442 lb; lV-on-1.5H structure slope Photo 5.



Sea-side view after attack of 1.57-sec, 0.63-ft waves; d = 0.70 ft; $W_{\rm A}$ = 0.589 lb; 1V-on-1.5H structure slope Photo 6.







Photo 7. End view after attack of 1.52-sec, 0.64-ft waves; $W_a \approx 0.589$ lb; 1V-on-1.5H structure slope




d = 0.65 ft;End view after attack of 2.42-sec, 0.63-ft waves; $W_A = 0.442 \text{ lb}$; IV-on-2H structure slope Photo 8.



Sea-side view after attack of 1.52-sec, 0.64-ft waves; d = 0.90 ft; W_{Δ} = 0.442 lb; lV-on-2H structure slope Photo 9.



= 0.85 ft;Sea-side view after attack of 1.73-sec, 0.71-ft waves; $W_a \approx 0.589 \text{ lb}$; 1V-on-2H structure slope Photo 10.



d = 0.95 ft;

APPENDIX A: NOTATION

A_1 and A_2	Surface area, ft ²
c	Coefficient
d	Water depth, ft
d/L	Relative depth
g	Acceleration due to gravity, ft/sec ²
H	Wave height, ft
H/d	Relative wave height
K _D	Stability coefficient
l a	Characteristic length of armor unit, ft
R _N	Reynolds stability number = $g^{1/2}H^{1/2}l_a/v$
Ť	Wave period sec, time
Wa	Weight of an armor unit, 1b
cot a	Reciprocal of breakwater slope
$\gamma_{\mathbf{a}}$	Specific weight of an armor unit, pcf
ν	Kinematic viscosity